


Residential Submittal

Filter Grille Access Door

MODEL: FG/AD Series




Standard Features:

- Access door designed for return air application
- 1/2" spaced louvers stamped into a hinged (non-removable) steel face frame
- Face set in an outer filter grille frame
- · Hinges parallel to longest side
- Hand operated lever for easy filter access
- Holds up to a 1" filter (not included) with filter retention tabs
- Rust resistant pre-coat with durable powder finish
- · Soft White

Options:

Access door, no louvers (AD)







BronzeStorm GrayCement Gray

Coffee Tan
Warm White
Glossy White

Aluminum Paint



FG/AD Frame Detail



Product Notes:

Filter grilles are manufactured 3/16" undersized nominal duct (outside dimension) for ease of installation. Air filter should be ½" to ½" undersize. Verify with air filter manufacturer for air specification to ensure a proper fit. Shoemaker filter grilles allow for installation of larger thickness filters (we offer 2" and 4" filter depths on specific models) which can reduce pressure drop on the overall system, improving air flow through the heat exchanger and allowing more time between filter changes. Contact customer service for more information.

Additional Information:

Submittal Notes

Project / Location:
Engineer:
Architect:
Contractor: